BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK_INDENT13893

APPROVED SCHEDULE - B

No. E/BTP/BBMP/E-PMT/07/2014-15, Date: 31.10.2014

Providing Street Signage Board in Ward No. 10 (Doddabommasandra), Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of VIJAYAKUMAR R	
				In Figures	In Words
1	80	1.35xk0.60x0.04 mtrs fixed in reinforced cement concrete poles of size 0.10x0.10x2.60 mtrs in cement concrete 1:1 1/2::3 proportion using 20 mm and down size graded metal machine mixed with 10 mm dia main steel bars and 8mm dia stripes show in drawing the board shall be provided with 12 mm thick cement plaster in cement mortar 1:3 on both	Each	5152.0	Rupees Five Thousand One Hundred Fifty Two Only
2	80	Providing and fixing sign board of size 60x60cm equilateral triangle using M.S sheet 5 mm thick with RCC pole of size 0.15x0.15x2.3 mtr made out of cement concrete 1:11/2:3 proportion using 20 mm and down size graded metal machine mixed with 10 mm dia main steel bars and 8 mm dia stirupps as shown in drawing, the poles shall be embedded in the ground for a depth of 0.6 mtrs with cement concrete 1:3:6 proportion, the board shall be fixed as per drawing and at the place indicated by the engineering charge of the work, the cost includes excavation, cost of all materials, cost of steel, centering, transportation charges, fixing charges etc. complete as per the direction of the engineer incharge of the work with all lead and lift as per direction of Engineer incharge of the work .	Each	3756.75	Rupees Three Thousand Seven Hundred Fifty Six and Seventy Five Paise Only
3	51.84	Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods etc. complete as per the direction of the engineer incharge of the work with all lead and lift as per direction of Engineer incharge of the work .	Cum	263.0	Rupees Two Hundred Sixty Three Only
4	51.84	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc. complete as per the direction of the engineer incharge of the work with all lead and lift as per direction of Engineer incharge of the work .	Cum	73.96	Rupees Seventy Three and Ninety Six Paise Only
5	28.8	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc. complete as per the direction of the engineer incharge of the work with all lead and lift as per direction of Engineer incharge of the work .	Cum	5816.52	Rupees Five Thousand Eight Hundred Sixteen and Fifty Two Paise Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P,
Bangalore - 560 092

6	524.8	Painting lines, dashes, arrows etc, on roads in two coats on new work :- painting lines, dashes, arrows etc on roads in two coats on new work with ready mixed road marking paint conforming to IS:164 on bituminous surface, including cleaning the surface of all dirt, dust and other foreign matter, demarcation at the and traffic control etc. complete as per the direction of the engineer incharge of the work with all lead and lift as per direction of Engineer incharge of the work .	Sqm	116.2	Rupees One Hundred Sixteen and Twenty Paise Only
7	35000	Painting new letter and figures of any shade with synthetic enamel paint block or any other approved colour to give an even shade complete as per specification, ("ii) Hindi (Matras commas and the like not to be measured and paid for half letter shall be counted as half) etc. complete as per the direction of the engineer incharge of the work with all lead and lift as per direction of Engineer incharge of the work .	Cm	0.69	and Sixty Nine Paise Only

Vijayakumar R

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92